BRUHATH BANGALORE MAHANAGARA PALIKE ,DASRAHALLI ZONE

**Office Of The Executive Engineer, Dasarahalli Division**

**SCHEDULE-B**

**NAME OF THE WORK**: Construction of RCC Drain in Right Side Shooting Building Road At Ravindra Nagar Wa No.13 Shettyhalli Sub Division.

| Sl No | Description Of Work | Unit | Qty | Rate To Be Quoted | |
|---|---|---|---|---|---|
| | | | | In Figures (Rs) | In Words (Rs) |
| 1 | 2 | 3 | 4 | 5 | 6 |
| 1 | KSRRB 300-3. Earthwork excavation by manual means in ordinary soil invoiving in average horizontal throw up to 2m & an average lift upto 1.5m , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specification MORTH/ Chapter 3. Page No. 142/ Item No. 19.1/ PWD SR 2016-17 | Cum | 694.00 | 175.96 | One Hundred Seventy Five Rupees and Ninety six Paisa Only |
| 2 | Removing B S Slab Drain And Stacking Page No25 Item No 5.32 PWD SR 2016-17 | Sqm | 837.00 | 65.72 | Sixty Five Rupees and Seventy Two paisa Only |
| 3 | KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2 Page No.12/ Item No. 4.3/ PWD SR 2016-17 | Cum | Available Course Aggregate: 73.85 | 4443.52 | Four Thousand Four Hundred Forty Three Rupees And Fifty Two Paisa Only |
| | | Cum | Remaining Balance Qty: 19.15 | 5159.02 | Five Thousand One Hundred Fifty Nine Rupees And Two Paisa Only |
| 4 | KSRB 4-1.5 : Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.43cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Page No.12/ Item No. 4.5/ PWD SR 2016-17 | Cum | 223.20 | 5874.52 | Five Thousand Eight Hundred Seventy Four Rupees And Fifty Two Paisa Only |
| 5 | KSRB 4-6.4 : Providing and removing centering, shuttering, strutting,. propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached1 pilasters, buttresses, plinth cilis and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 Page No.15/ Item No. 4.31/ PWD SR 2016-17 | Sqm | 2232.00 | 310.58 | Three Hundred Ten Rupees And Fifty Eighty Paisa Only |

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Dasarahalli Division

Scanned by CamScanner

| | | | | | |
|---|---|---|---|---|---|
| 6 | KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.Specification No. KBS 4.6.3, TMT bars 'Fe 500. Page No. 17/ Item No. 4.46.2/ PWD SR 2016-17 | Tones | 13.39 | 74331.44 | Seventy Four thousand Three Thirty One Rupees And Forty Four Paisa Only |
| 7 | Providing & laying reinforeced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Complete as per specfications. | Sqm | 585.00 | 1680.00 | One Thousand Six hundred Eighty Rupees Only |

Signature Of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer,
Dasarahalli Division,

Scanned by CamScanner